

University of Nebraska - Lincoln

DigitalCommons@University of Nebraska - Lincoln

Theses from the Architecture Program

Architecture Program

Spring 5-6-2011

Place [for] the Children

Heather Hudson

University of Nebraska-Lincoln, heather.hudson@huskers.unl.edu

Follow this and additional works at: <https://digitalcommons.unl.edu/archthesis>



Part of the [Architecture Commons](#)

Hudson, Heather, "Place [for] the Children" (2011). *Theses from the Architecture Program*. 106.
<https://digitalcommons.unl.edu/archthesis/106>

This Article is brought to you for free and open access by the Architecture Program at DigitalCommons@University of Nebraska - Lincoln. It has been accepted for inclusion in Theses from the Architecture Program by an authorized administrator of DigitalCommons@University of Nebraska - Lincoln.



place [for] the children

by Heather Hudson

A Terminal Project
Presented to the Faculty of
The College of Architecture at the University of Nebraska
In Partial Fulfillment of Requirements
For the Degree of Master of Architecture
Major: Architecture
Under the Supervision of Professor Tim Hemsath
Lincoln, Nebraska
May 2011

abstract

Due to changing social and economic trends, enrollment in child care has become customary for the large majority of children under the age of five in the U.S. Although the importance of the early years has slowly begun to gain more recognition, early childhood development and education is still not viewed as the imperative societal issue that it demands. As the widespread environment for raising children in the U.S. has gradually moved from the informal atmosphere of the home to the formal settings of a child care center, the impact of the built environment on children's development has often been overlooked. Brain research indicates that children are born ready to learn, while absorbing every aspect of their environment.

Place [for] the children is a graduate design thesis that explores the relationship between children and architecture asking the question, how can architecture serve as an educational aid in early learning? The intent was to create a multisensory environment in which the architecture, playing an integral role in the educational process, fosters experiential learning. The goal was to help children learn how to learn, while provoking discovery and promoting creative thinking. This project is an investigation into how early childhood design can be rethought, redefining a daycare center as an educational facility in which children learn through interactions and experiences, stemming from their environment.

how can architecture serve as an educational aid in early learning?

table of contents

abstract

contents

research

- the need...6
- the importance...10
- the challenge...12

analysis

- precedents...22
- design analysis...32
- conclusions...36
- program...40
- site...50

initial proposal

- schematic design...58

process

- program...68
- design concepts ...70

final proposal





- physical model...86
- elements of design...88
- moments of learning...102
- looking back...115


bibliography

acknowledgements

research


Due to the changing social and economic trends, enrollment in **child care** has become customary for the large majority of **children** under the age of five in the U.S. In 2008, there were more than 11 million children in child care, placing care giving among the fastest growing occupations in the U.S. (Olds, 2001) It is estimated that 60 million square feet of space will be required each year to keep up with the vigorous rise in children needing care across the country.






U.S. Department of Education, Oct. 1976-Oct. 2008


*Quality rating based on the Early Childhood Environment Rating Scale (ECERS). The rise in enrollment has **increased the need for conscious design**, because the majority of centers have responded to the demand with quantity instead of quality. In May 2010, the National Institute of Child Health and Human Development (NICHD) released a report that found that **high-quality child care has a long-lasting impact on a child's development**, behavior and cognitive abilities. (National Institutes of Health, 2011)



% DISTRIBUTION OF QUALITY*
RATING OF CENTER-BASED
PROGRAMS AT AGE 4

U.S. Department of Education, 2005-06






RIGHTS AND POTENTIAL OF ALL CHILDREN


As the widespread environment for raising children in the U.S. has gradually moved from the informal atmosphere of the home to the formal settings of a child care center, **the impact of the built environment on children's development has often been overlooked.** Although the importance of the early years has slowly begun to gain more recognition, early childhood development and education is still not viewed as the **imperative societal issue** that it demands. The investment in the first five years can create long-term savings to other public systems such as education and health care, as well as mold the future of society. **Architecture involves designing for the future and children represent our future.**

the importance

science of early childhood



Brain research indicates that **children are born ready to learn**. The neural connections for different functions develop sequentially, with the growth of the brain reaching 80% adult size by the age of three and 90% by age five. “Early experiences determine whether a child’s developing brain architecture provides a strong or weak foundation for all future learning, behavior, and health. The brain is built over time, from the bottom up and a substantial proportion is constructed during the early years.” (Center on the Developing Child, 2007) With the environment having a direct effect on development, **architects need to respond** to this essential need for quality child care design.



Unlike an adult’s relationship to the environment, children use places for sensory experiences rather than for pre-defined purposes. Through sensorial exploration, **children absorb every aspect of their environment**. Attention needs to be given to the effects of the built environment on a child’s development.



children's environmental needs

movement

- .movement is considered to be the foundation for **COGNITIVE** development
- .large muscle activity promotes **PHYSICAL** development
- .indoor supports for large muscle activity (climbers, lofts, platforms, nets, ladders, bouncy surfaces, movement areas, and equipment with movable parts)
- .opportunities to run, climb, swing, slide, and crawl outdoors
- .resolves the tension between children's need to move and caregivers needs to organize the movement



comfort

- .moderate levels of stimulation create feelings of comfort
- .difference-within-sameness--variation in architectural elements: scale, floor height, ceiling height, and lighting, variety in texture of finish materials, and the presence of soft elements (carpets, couches, and pillows)
- .opportunities to create separate “places” for engaging in different activities (warm and cozy, hard and sterile, dark or light, noisy or quiet)
- .prevents boredom and discomfort by enabling children to seek out stimulation according to their changing moods, important to their **EMOTIONAL** development



Day, 2007

The task of designing a child care center demands an understanding of how children develop and what they need. A child's relationship to the built environment is unlike an adult's, and close attention is to be paid in how the design of their surroundings influence their well being. As a result of the investigation of children's perceptions of their built surroundings, a more sensitive understanding of children's spatial culture emerged. Catering to children's environmental needs of movement, comfort, competence and control, the design should have a positive influence on their social, physical, cognitive, and emotional development. Instead of 'placing' the children in an environment, a place shall be created 'for' them.



competence

- .supportive environment that helps children fulfill their own needs, execute tasks easily, manage their own materials, and control their own movement from place to place
- .variety of things to do--allows children to find things at which they can succeed
- .variety of places--reduces overall scale of room and helps children perceive possibilities and limits of each activity
- .well-organized/accessible things and places--invites child use, helps focus attention, important to their **COGNITIVE** development



control

- .environment determines how children meet and how easily they can do things together, affecting their **social** development
- .privacy: window seats, platforms, cubbyholes, fiberboard barrels with cutouts, and small enclosures (maintain balance between access to child and the child's privacy)
- .predictability: unpredictable environments increase a child's lack of ease and control (doors and windows are informative, making the center "decipherable" by the child)
- .orientation: views provide **PHYSICAL** and **EMOTIONAL** healing benefits, as well as **COGNITIVE** benefits by increasing their knowledge of the natural world; children need to sit so their backs are against the walls to experience a sense of environmental safety and control

security  independence

childhood: a journey of evolving needs



Day, 2007



provides for

developmental skills

social

physical

cognitive

emotional


A child's development of social, physical, cognitive, and emotional skills is related to the closeness of their relationship with their caregiver. The quality of this relationship is dependent on the environment, resulting directly from the design, in which the caregiver raises the child. Even though the relationship is vital, research shows that **children remember places and sensations far more than they remember people.** (David, 1976) Unlike adults, every detail matters, as they deeply affect children.

multisensory learning

touch

.most critical sense until age 3
.texture, materiality, form, resistance

materiality



stone, earth, brick

.cold & hard, visually
.texturally warm
.‘old’ associations,
protectively enclosing,
durable, rooted in place



wood

.touch-friendly, warm,
attention-tolerant
.lighter and ‘newer’, but still
rooted in place



glass, steel

.unfriendly--products of
machines, not life
.feels ‘new’, open and
expansive
.views and exposure

sight

.visual design needs multisensory support
.light, color, shape, form

exciting, active



calming, quiet




“They need - and seek - to experience things with their **WHOLE** bodies and through **ALL** their senses.”

-Christopher Day, Environment and Children

smell


- .conveys info of how we relate to things
- .building and furnishing materials, plants



smellscape

hearing

- .balance takes place in the ear
- .object density, materiality



taste

- .lines, shapes, textures, and materials provide imagery to our taste buds



Gherkin






























Casa Battlo













Jewish Museum



analysis

	adaptive re-use		stand-alone	
case study 1 [UNL Children's Center]	case study 2 [Prairie Hill Learning Center]	case study 3 [Knowledge Beginnings]	case study 4 [Colorful Minds]	
<p>adaptive re-use of Whittier Junior High School .13,000 square feet .150 children .6 weeks-5 years</p> 	<p>adaptive re-use of farmhouse and new construction of Renewable Energy Education Center .3,700 square feet (size of new building only) .75-80 children .11/2 to 1.4 years (does not care for infants, although first years of a child's life are highly critical to his or her development)</p> 	<p>corporate-owned .170 children .6 weeks-10 years</p>	<p>individually-owned .100 children .6 weeks-10 years</p> <p>built on the edge of a commercial district, adjacent to a residential neighborhood, the neighbors were unhappy</p> 	
<p>center separated into 3 families, each consisting of an infant, toddler, and preschool room children stay in their family as they move up in the center, allows for smooth transitions</p> 	<p>building built into the ground reduces the scale of the entrance</p> 	<p>building built into the ground reduces the scale of the entrance</p> 	<p>uncoiled, uncoupled reception desk reduces comfort and control</p> 	
<p>varied floor height creates lift for views and storage</p> 	<p>variety of activities for children to choose from, located in a specific sequence</p> 	<p>arbitrary tile/carpet layout reduces comfort and competence</p> 	<p>unreachable cubbies do not provide for competence</p> 	
<p>big, low windows into hallway assists with orientation and predictability</p> 	<p>each room has direct access to outdoor play area</p> 	<p>each room has direct access to outdoor play area</p> 	<p>no windows from hallway into the classrooms restrict control</p> 	
<p>ceiling lowered to reduce scale natural light floods interior</p> 	<p>views → light blocked windows don't allow for light or views</p> 	<p>views → light large, low windows provide natural light and views outside</p> 	<p>views → light large, low windows provide natural light and views outside</p> 	
<p>natural wall colors and furniture variety of "places" with a variety of things to do</p> 	<p>self-teaching and self-correcting materials concrete thinking abstract thinking</p> 	<p>orientation assisted with one colored wall in each room</p> 	<p>orientation assisted with distinct floor colors in each room</p> 	
<p>water exploration encouraged slide on hill is safer and less imposing</p> 	<p>sensory nature exploration environmental stewardship</p> 	<p>no physical movement encouraged</p> 	<p>no outdoor play area at this time, no physical movement encouraged</p> 	
<p>Reggio Emilia, Creative Curriculum children are directly involved in the choices they have in the classroom children learn through hands on activities that have been purposely planned children stay in families (infant, toddler, and preschool rooms) outside time is key element Jean Piaget & Erik Erikson</p>	<p>Montessori home-like & consistent atmosphere throughout the day .promotes individual growth as well as caring for others and the Earth situated in a farm-like environment that fosters respect for self, others, animals, and nature .prepared environment: materials organized into 5 basic categories of practical life, sensorial, mathematics, language, and cultural subjects</p>	<p>NAEYC Accreditation, Thematic Accreditation: Early Learning as LEED; Architecture (helpful rating system but time-consuming and often misses the bigger picture) .research-based educational programs</p>	<p>unknown, NAEYC member incorporates Nebraska's Early Learning Guidelines (minimum standards) social & emotional development, approaches to learning, health & physical development, language & literacy development, mathematics, science, creative arts</p>	
<p>Designed by RDG as part of the renovation of Whittier Junior High, the building was revitalized with a new program that gave the abandoned building a new use. .movement: indoor and outdoor play areas provide opportunities to run, climb, and slide .comfort: varied ceiling and floor heights reduces scale .competence: variety of things to do in a variety of places reduces overall scale .control: large, low windows provide interior and exterior views, offering predictability and orientation</p>	<p>Designed by James Dyck of The Architectural Partnership, the school consists of a building for young children, a renovated farmhouse for the primary children, and a new Renewable Energy Education Center for the elementary children .movement: opportunities for exploration in a farm-like environment .comfort: opportunities to create separate "places" for different activities .competence: child-initiated activities builds concentration; well-organized/accessible things and places; children involved in cooking, cleaning, etc. .control: large, low windows provide interior and exterior views, offering predictability and orientation</p>	<p>The lack of space in the crowded rooms take away from a child's emotional development, due to the inability of a child being able to spend some time apart from others. .movement: no indoor play area and outdoor play area does not encourage movement .comfort: scaled entrance, but crowded rooms do not allow for separate "places" to do a variety of activities .competence: reading area helps focus attention .control: orientation assisted with views to the outside as well as one different colored wall in each room</p>	<p>The design of Colorful Minds is not scaled down to the size of a child. .movement: no indoor or outdoor play area .comfort: no variation in scale, ceiling or flooring height, lighting, texture of finish materials, or soft elements .competence: unreachable cubbies and high bathroom sinks do not allow children to execute tasks on their own .control: orientation assisted with views to the outside as well as different colored floors in each room; interior predictability is impossible with no windows into the hallway</p>	
<p>PROS .sustainable, resourceful, adaptive, and innovative .gives use to a vacant/abandoned building, enabling revitalization .exhibits how something better can be created from a degenerating condition .exposure to children at a young age helps their understanding of sustainable methods</p>	<p>CONS .removal of asbestos, lead paint, etc. can be difficult .exterior structure restricts design</p>	<p>PROS .freedom to design without restrictions .no existing conditions to design around</p>	<p>CONS .costly .uniformity and flawlessness make it difficult to give contemporary buildings the quality of spirit native to many older buildings</p>	

site/size/ages	<p>.adaptive re-use of Whittier Junior High School .13,000 square feet .150 children .6 weeks-5 years</p>  
building	 <p>center separated into 3 families, each consisting of an infant, toddler, and preschool room</p> <p>children stay in their family as they move up in the center, allows for smooth transitions</p> <p>comfort, control</p>
classroom	 <p>varied floor height creates loft for views and storage</p>  <p>views outside</p> <p>storage</p> <p>movement, comfort, control</p>
circulation	 <p>big, low windows into hallway assists with orientation and predictability</p>  <p>control</p>

lighting	 <p>ceiling lowered to reduce scale</p> <p>natural light floods interior</p>  <p>comfort, control</p>
color/materials	<p>natural wall colors and furniture</p> <p>variety of “places with a variety of things to do”</p>  <p>comfort, competence</p>
outdoor play	<p>water exploration encouraged</p> <p>slide on hill is safer and less imposing</p>   <p>movement, competence</p>
philosophy	<p>Reggio Emilia, Creative Curriculum</p> <ul style="list-style-type: none"> .children are directly involved in the choices they have in the classroom .children learn through hands on activities that have been purposely planned .children stay in families (infant, toddler, and preschool rooms) .outside time is key element .Jean Piaget & Erik Erikson

adaptive re-use

case study 1 [UNL Children’s Center]

Designed by RDG as part of the renovation of Whittier Junior High, the building was revitalized with a new program that gave the abandoned building a new use.

.movement: indoor and outdoor play areas provide opportunities to run, climb, and slide


.comfort: varied ceiling and floor heights reduces scale

.competence: variety of things to do in a variety of places reduces overall scale


.control: large, low windows provide interior and exterior views, offering predictability and orientation

site/size/ages


.adaptive re-use of farmhouse and new construction of Renewable Energy Education Center
 .3,700 square feet (size of new building only)
 .75-80 children
 .1 1/2 to 14 years (does not care for infants, although first years of a child's life are highly critical to his or her development)



building



classroom




variety of activities for children to choose from, located in a specific sequence

movement, comfort, control



circulation




each room has direct access to outdoor play area

control



lighting



comfort, control



color/materials


self-teaching and self-correcting materials

concrete thinking



abstract thinking

competence



outdoor play

sensory nature exploration



environmental stewardship

movement, competence



philosophy

Montessori

- .home-like & consistent atmosphere throughout the day
- .promotes individual growth as well as caring for others and the Earth
- .situated in a farm-like environment that fosters respect for self, others, animals, and nature
- ."prepared environment": materials organized into 5 basic categories of practical life, sensorial, mathematics, language, and cultural subjects

adaptive re-use

case study 2 [Prairie Hill Learning Center]







Designed by James Dyck of The Architectural Partnership, the school consists of a building for young children, a renovated farmhouse for the primary children, and a new Renewable Energy Education Center for the elementary children

.movement: opportunities for exploration in a farm-like environment


.comfort: opportunities to create separate "places" for different activities

.competence: child-initiated activities builds concentration; well-organized/accessible things and places; children involved in cooking, cleaning, etc.

.control: large, low windows provide interior and exterior views, offering predicatability and orientation

site/size/ages	<p>.addition to an existing elementary school .12,120 square feet .70 children .4-5 years</p> <div> <div>Cougar Elementary School</div> <div>Pre-K</div> <div>Manassas Park Elementary School</div> </div>
building	<div>  <p>hallway breakout space creates separate places for activities</p> </div>  <p>competence, control</p>
classroom	<div>  <p>cave-like reading nook offers privacy and views</p> </div>  <p>comfort, control</p>
circulation	<div>  <p>scaled entrance door</p> <p>4'</p> </div>  <p>comfort</p>


lighting



color/materials



outdoor play



philosophy

unknown, state standards








.Virginia's Foundation Blocks for Learning
.comprehensive standards for 4-year-olds: literacy, mathematics, science, history & social sciences, physical and motor development, and personal & social development
.creates a 'school in the woods' with strong relationship with adjacent mixed-oak forest & draws from recreational opportunities

addition


case study 3 [Manassas Park Pre-K]

VMDO's design of Manassas Park Pre-K brings nature inside. Learning about their environment will increase the children's social and environmental awareness.

- .movement:** outdoor classroom allows large muscle activity
- .comfort:** door and floor variations in scale; interior flooded with natural light and visual/direct connections with nature
- .competence:** hallway breakout space and reading nook offer variety of places to do different things
- .control:** reading nook offers privacy and orientation, with views out to nature

<p>site/size/ages</p>	<p>.connected to an existing elementary school .200 children .6 weeks-5 years</p>  
<p>building</p>	<div data-bbox="982 495 1249 771"> </div> <p>administration area includes community outreach programs and educational facilities to give parents and educators valuable resources</p> <p>competence, control</p> 
<p>classroom</p>	 <p>one-way glass allows for observation by parents, teachers, and researchers</p> <p>control</p> 
<p>circulation</p>	 <p>varied ceiling heights reduce scale and allows natural lighting in the hallways</p> <p>movement, comfort</p> 

lighting




large, low windows provide natural light and views outside, needs soft elements



comfort, control

color/materials



orientation assisted with one colored wall in each room



control

outdoor play

opportunities for gardening, riding, music, art, climbing, and sliding outside



movement, comfort, competence, control

philosophy

Reggio Emilia, Educare

- .serves low-income families, Susan Buffett Foundation
- .community outreach programs and educational facilities combine to give parents and educators valuable resources
- .research-based practices and strategies
- ."continuity of care": promotes secure teacher-child attachment

addition

case study 4 [Indian Hills Educare]


Designed by RDG, the second Educare facility in Omaha connects to Indian Hills Elementary school.

.movement: outdoor play area supports large muscle activity including riding, climbing, and sliding; indoor play area available in the hallways (difficult to supervise?)

.comfort: varied ceiling and floor heights reduce scale, interior flooded with natural light




.competence: variety of places to do different things

.control: orientation assisted with colored walls in each room





design analysis

classroom




circulation



insecure, attention-distracting? or anticipatory, safety precaution?

lighting

Constantly varying light quality nourishes both eyes and light sensitive organs - essential for healthy child development. (Day, 2007)




color/materials

Prior to age 5 or 6, children are more likely to remember color than form. (Day, 2007)

exciting, active

avored by young children up to 6 years of age [activity-led, not feeling - or thought-led]



calming, quiet




Until about 7 years of age, children experience their inner world at least as vividly as their material surroundings, 'inner colors - complementary after-images - often have stronger influence on mood.' (Olds, 2001)

outdoor play

Richard Louv has exposed evidence that children today are at risk for what he calls “Nature-Deficit Disorder,” due to the lack of connection children have with nature. (Louv, 2008)


nature

- .neural processing
- .emotional outlet
- .knowledge about the world





philosophy

Reggio Emilia




Montessori






conclusions

classroom



Dull rooms increase dependence on *things*. As thing-dependence is hardly sustainable, it's better if rooms *themselves* stimulate imagination. Rooms specifically designed for this need very little in the way of consumerist 'props.' (Day, 2007)


circulation



anticipatory, safety precaution


allows orientation and predictability

lighting



color/materials

- .unified, but distinct color scheme for each room
- .use colors inspired from nature




open-ended
natural materials




imagination, creativity and
symbolic (abstract) thinking


Arbor Day Foundation, 2010


outdoor play




philosophy











daily timeline [infant]

travel to
arrival
approach
entry
transition
breakfast
free play
diaper change
nap
outdoor play
small group activity
diaper change
lunch
diaper change
nap
diaper change
snack
outdoor play
free play
dismissal
departure
travel from




daily timeline [toddler]

travel to
arrival
approach
entry
transition
breakfast
classroom
individual activity
restroom
large group activity
outdoor play
small group activity
restroom
lunch
restroom
nap
restroom
snack
outdoor play
individual activity
small group activity
dismissal
departure
travel from




daily timeline [3-year-old]

travel to
arrival
approach
entry
transition
breakfast
classroom
individual activity
restroom
large group activity
outdoor play
small group activity
restroom
lunch
restroom
nap
restroom
snack
outdoor play
individual activity
small group activity
dismissal
departure
travel from








daily timeline [4-5-year-old]

travel to
 arrival
 approach
 entry
 transition
 breakfast
 classroom
 individual activity
 restroom
 large group activity
 outdoor play
 small group activity
 restroom
 lunch
 restroom
 nap
 restroom
 snack
 outdoor play
 individual activity
 small group activity
 dismissal
 departure
 travel from



daily circulation






45% of the statewide increase
in total number of
children at risk 0-5


RURAL NEBRASKA


55% of the statewide increase
in total number of
children at risk 0-5

Nebraska Children and Families Foundation, 2010

Nearly 7,000 children in Lancaster County are at risk - lacking a nurturing home, a stable family, or a safe neighborhood. Currently about 50% of the students in Lincoln Public Schools, preschool through fifth grade, live in poverty. The site of Belmont elementary school was chosen as a case study, with 72% of the students living in poverty. The infill site will allow the early learning center to become part of the existing community's infrastructure.







residential housing

swimming pool

portables

19 students X 3=57 students (remove)

park

school

residential


4th Street

Belmont Elementary School

750 students

pre-k=50 children (move to new center)

1st-5th grade=700 students



qualify for free
or reduced meals

Belmont Recreation Center

Belmont Community Center




school site 3 site 2 site 1 park pool site 4




initial proposal

The aim of this project was to serve as a case study investigating how **architecture can serve as an educational aid in early learning**. In order to create an engaging environment for learning, it must provoke discovery and promote creative thinking. Using the philosophy of Reggio Emilia, the intent was to create a multisensory environment in which the architecture, playing an integral role in the educational process, fosters experiential learning. Rather than teaching through formal lessons, the Reggio Emilia approach uses the **environment to inform and engage** the user. The environment is viewed as the third teacher, in which the space is designed to encourage encounters, communication, and relationships. Children's play is their form of learning, and the goal is to help children learn how to learn. The child-initiated activities allow one to learn from the interactions and create his or her own understanding in relation to them. The idea was for the 'emergent curriculum' to stem from the **architecture that emerges** into activities, leading to discovery, ultimately resulting in learning. Spaces evolve according to each age group and general volumetrics are combined with the more intimate scale that is necessary for a child. Through the use of space, light, materiality, and color, the **sensorial relationship between children and architecture** is explored. Rather than placing children in an arbitrary environment, a place was created [for] them, where the design is integral to their education and development.






schematic design




nurturing balanced inspiring
 dark light
 solid transparent
 quiet noise
 secure open
 calm excited
 quiet active
 defined flexible
 order mystery
 safety wonder
 down up
 low high
 under over
 feeling thinking
 activity thought


INFANT → TODDLER → PRESCHOOL



emergent architecture




forms → activities → discovery → learning



2 families
[reduce scale]




distinct rooms
[assists orientation]



central
courtyard
[flow from
inside to nature]




organic shape
[natural form]



distinct rooms +
courtyards
[naturally lit interior]




organic shape +
interior courtyards



distinct rooms +
courtyards +
form according
to age



organic shape +
form according
to age







edge conditions



straight boundaries



curvilinear boundaries



Taschen, 2001



community




flow




nature




common area eliminates need for corridors




direct link from learning spaces to outdoor spaces creates an osmotic relationship




PUBLIC





sub-common spaces outside rooms provide transitional filter zones, encouraging easy, unhurried exchange of information















varied transparencies allow communication in, out, and between




2nd skin serves as a backdrop onto which the children's ideas become part of the school's learning program and culture, allowing interior and exterior communication by the building





PUBLIC

PRIVATE



surrounding a central common area, the children's spaces, divided into two families to reduce scale, are on the south side of the building

administrative area:

- .entry vestibule_80 sq. ft.
- .reception_80 sq. ft.
- .director's office_140 sq. ft.
- .asst. director's office_140 sq. ft.
- .conference room_200 sq. ft.
- .teacher resource/workroom_300 sq. ft.

administration
860 ft.2

parent/public:

- .parent resource room_180 sq. ft.
- .large meeting room_600 sq. ft.
- .women/men's restroom_400 sq. ft.

parent/public
1180 ft.2

kitchen/dining/indoor play:

- .kitchen_500 sq. ft.
- .indoor play/dining area_32 children X 50'=1600 sq. ft.
- .storage room_350 sq. ft.
- .mechanical room_300 sq. ft.
- .electrical room_100 sq. ft.
- .custodian closet/laundry_150 sq. ft.
- .service entrance

kitchen/dining/
indoor play
3000 ft.2

commons area_900 sq. ft.

family A:

- .infants (birth-18 mos.)_2 teachers X 1:4 ratio=8 children X 100'=800 sq. ft.
- .toddlers (18 mos.-3 yrs.)_2 teachers X 1:5 ratio=10 children X 75'=750 sq. ft.
- .toddler restroom_130 sq. ft.
- .preschool 1 (3 yr.-olds)_2 teachers X 1:7 ratio =14 children X 75'=1,050 sq. ft.
- .preschool restroom_130 sq. ft.
- .preschool 2 (4-5 yr.-olds)_2 teachers X 1:9 ratio = 18 children X 75' =1,350 sq. ft.
- .preschool restroom_130 sq. ft.





family A
4000 ft.2
[50 children]

family B:


- .infants (birth-18 mos.)_2 teachers X 1:4 ratio=8 children X 100'=800 sq. ft.
- .toddlers (18 mos.-3 yrs.)_2 teachers X 1:5 ratio=10 children X 75'=750 sq. ft.
- .toddler restroom_130 sq. ft.
- .preschool 1 (3 yr.-olds)_2 teachers X 1:7 ratio =14 children X 75'=1,050 sq. ft.
- .preschool restroom_130 sq. ft.
- .preschool 2 (4-5 yr.-olds)_2 teachers X 1:9 ratio = 18 children X 75' =1,350 sq. ft.
- .preschool restroom_130 sq. ft.

family B
4000 ft.2
[50 children]


=13560 ft.2




reduced scale




connected program layout



composite form








parking buffer








Following the natural contours of the site, the building has a four foot elevation change, sequencing from the public spaces to the private spaces. Changes in ceiling heights, along with the changing floor heights create a range in scale, important to a child's developing spatial awareness.







Even though many of my ideas changed throughout the design process, with several of them not making it into the final proposal, they all had an influence on the design. Through iterations of physical and digital study models, I explored different concepts related to mass, form, enclosure, and materiality. One idea included a 2nd skin that wrapped the public areas of the building, as well as forming outdoor protected spaces for the younger children. This later evolved into the concept for the interior walls.




MASS




- .shaped by human thought
- .needed for order, concentration, and doing

FORM



- .shapes of nature, movements, all living things
- .needed for protection, socialization, and being

ENCLOSURE




- .transparency allows exposure to nature
- .assists with orientation and wayfinding



concrete

- .rigid, ordered exterior
- .protectively enclosing and durable




wood

- .organic, natural interior
- .touch-friendly, warm, attention-tolerant
- .connects social areas and filters into nature



glass

- .open and expansive to nature
- .allows views to nature and circulation, assisting with orientation



This diagram illustrates putting together the concepts of the edge conditions with the concepts of natural vs. rigid form and materials. Interactions with nature encourage environmental awareness while interactions within the interior encourage social awareness.



final proposal

SITE PLAN

1/128"=1'

An infill site, as an addition to an existing elementary school will allow the early learning center to become part of the community's existing infrastructure, serving as a case study for the argument of early learning as an imperative societal issue. Located on the northeast corner of Belmont Park, the early learning center takes advantage of the views of nature as well as accessibility from 14th Street.

natt Street


Lewis Avenue


1 4th Street

Belmont Park

Belmont Elementary School

[81]






PLAN

$1/32'' = 1'$

The concept of edge conditions for the overall form is repeated on the interior in the individual rooms. In addition to its acoustic factor, non-linear rooms create more places for learning to take place. In the common area, the ramps follow the natural contours of the site, sequencing from the public spaces to private spaces. Another ramp is present in the central courtyard, accessible from the dining area, connecting to the roof garden.








SECTION
1/16"=1'





physical model







elements of design









[courtyard] centrally located, providing a link to pull nature in and creating a constant focus on nature




[interior] vertical wood slats create a natural form in the interior that serves as a connector to social and outdoor spaces while encouraging interaction through its dynamic transparency vs. opacity





[exterior] concrete siding creates a rigid protection for the interior



[columns] steel columns form the supporting structure

[floors] following site contours, floors sequence from public to private

entry exterior

The front entry serves as a transparent threshold, creating an inviting environment for children as they approach the center. Its apparent from the front entry that nature is infused in the building.




entry interior

The constant view of the courtyard assists with orientation and wayfinding, providing **control**. The water tube collects filtered rainwater from the roof, allowing children to experience water in a unique way while creating a relaxing feature in the common area.



common area

The common area is an interconnected space providing views of multiple levels of learning while exposing children to different spatial complexities. The space encourages social interaction of multiple age levels.





outdoor play area

Window heights are placed according to the heights of children, with wood window frames creating a connection from the interior to the exterior. Orientation to the exterior provides control, with views offering **physical** and **emotional** healing benefits, as well as **cognitive** benefits of increasing their knowledge of the natural world. Lower windows not only frame views specifically for children, but also create window seats for the children to inhabit.




moments of learning






A variety of spaces provides opportunities for small and large group learning, offering comfort in creating separate “places.”

[Is this a step or a seat?]









Vertical wood slats provide a multisensory experience including the senses of sight, touch, smell, and sound while also creating a dynamic experience of a changing perspective as a child moves along the wall. The cool green color of the children's room serves as a contrast to the warm color of the wood.

[Is this a wall or a window?]







The central courtyard pulls nature into the interior while piquing a child's curiosity of inside vs. outside. The water feature allows children to experience flowing water using their senses of sight, sound and touch.

[Are we inside or outside?]

outside


inside

outside?

inside


outside






Exposed earth in the common area gives children a first-hand view of the earth in a way that they would not normally experience. Unveiling not only the layers of the earth, but the ecology that takes place just below their feet.

[Are we above ground or below?]








The roof garden provides learning opportunities for gardening while providing a multisensory space including sight, touch, smell, and taste. For example, petunias attract butterflies, creating a ecological learning opportunity. The green roof also allows children to relate to the activities taking place on multiple levels.

[Is it a garden or a roof?]





looking back



While serving as a case study showing how architecture can be used as an educational aid in early learning, the result of my thesis raised as many questions, if not more, than it answered. The final proposal of place [for] the children is a mere snapshot into the possibilities of how architecture can have an impact on the education and growth of children. If nothing else, I hoped to have opened someone's eyes to the importance of the environment on a child's development. Slowly, early childhood design is gaining recognition and beginning to receive the attention that it deserves.

As mentioned earlier, children absorb every aspect of the environment, leaving no detail too small for design. I often found it difficult to devote the same amount of rigor and design to elements ranging from the overall form of the building down to the details of the handrails. Knowing that learning occurs everywhere, it was a challenge to design every aspect of my project to the degree necessary for my chosen program of an early learning center.

This thesis experience was unlike any other that I have had in my academic career. Through this process, I have learned lessons about myself, as a designer, that will be invaluable to me as I move forward in the profession.

American Community Survey. U.S. Census Bureau. March 24, 2011. www.census.gov/acs/www (accessed September 15, 2010).

Arbor Day Foundation & Dimensions Educational Research Foundation. "The Value of Open-Ended, Natural Materials." 2010.

Center on the Developing Child. "A Science-Based Framework for Early Childhood Policy." National Symposium on Early Childhood Science and Policy. Cambridge: Harvard University, 2007.

Day, Christopher. *Environment and Children*. Oxford: Elsevier Ltd., 2007.

Dudek, Mark. *Children's Spaces*. Burlington: Architectural Press, 2005.

Dudek, Mark. *Kindergarten Architecture*. Chapman & Hall: London, 1996.

Dyck, James A. *The Case for the L-Shaped Classroom: Does the Shape of a Classroom Affect the Quality of Learning That Goes Inside It?* Principal, November 1994.

David, T.G. and E. Prescott, *Concept Paper on the Effects of the Physical Environment on Day Care*. Pasadena, CA: Pacific Oaks College, 1976.

FPG Child Development Institute. *Environment Rating Scales*. Carrboro, NC, 2005.

Goldschmied, Elinor and Sonia Jackson. *People Under Three - Young Children in Day Care*. London: Routledge, 1994.

Harner, D.P. "Effects of Thermal Environment on Learning Skills." *Educational Facility Planner* 12.2. 1974. 4-6.

Hertzberger, Herman. *Lessons for Students in Architecture*. Rotterdam: Uitgeverij 010 Publishers, 1991.

Jensen, Eric. *Environments for Learning*. San Diego: Brain Store, 2003.

Kittner, Sam and Prakash Patel. *VMDO Architects*. Charlottesville, VA: 2011.

Kroner, Walter. *Architecture for Children*. Stuttgart: Karl Kramer Verlag, 1994.

Louv, Richard. *Last Child in the Woods: Saving Our Children from Nature-Deficit Disorder*. Chapel Hill, NC: Algonquin Books of Chapel Hill, 2008.

National Association of Child Care Resource and Referral Agencies. “NACCRRRA Annual Report.” Arlington, VA, 2010.

National Institutes of Health. Eunice Kennedy Shriver National Institute of Child Health and Human Development. 2011. www.nichd.nih.gov (accessed September 13, 2010)

Nebraska Children and Families Foundation. Advancing Early Childhood Policy. 2010. www.advancingearlychildhood.org (accessed November 16, 2010)

Nelson, C. A., in *Neurons to Neighborhoods*. Shonkoff, J. & Phillips, D. (Eds.), 2000.

Norberg-Schulz, Christian. *Genius Loci: Towards a Phenomenology of Architecture*. New York: Rizzoli International Publications, Inc., 1980.

Olds, Anita Rui. *Child Care Design Guide*. Quebecor: McGraw-Hill Companies, 2001.

Pallasmaa, Juhani. *Eyes of the Skin: Architecture and the Senses*. Chichester: Wiley-Academy, 2005.

Taschen. *Harvard Design Guide to Shopping*. Cambridge, MA: The President and Fellows of Harvard College, 2001.

U.S. Department of Education, National Center for Education Statistics, *Early Childhood Longitudinal Study, Birth Cohort, Longitudinal 9-month—Preschool, 2005-06*. www.nces.ed.gov (accessed September 23, 2010)

U.S. Department of Education, National Center for Education Statistics, *Preprimary Enrollment, 1970 and 1975*. U.S. Department of Commerce, Census Bureau, *Current Population Survey (CPS)*, Oct. 1976-Oct. 2008. www.nces.ed.gov (accessed September 23, 2010)

acknowledgements

I would like to thank all those that have helped me throughout this process. Without them, I would not have been able to complete this project.

My thesis mentor, Tim Hemsath, for his thoughtful input and continued support throughout this entire process. Thank you for your criticism as well as pushing me to always do my best.

My guest critics - Rumiko Handa, Peter Hind, Kathy Ankerson, and Nate Krug, for offering their time and input. Your suggestions were always well directed and I want to thank you for encouraging me to look at my design from different perspectives.

My fellow students, for the memories, thank you for your willingness to offer help and feedback. My friends, who were always there for me, thank you for your continued support.

Finally, my family, for their unending love and support throughout these past six years. Words cannot describe how grateful I am to have such amazing parents that have helped me get through the good times and the bad. Always reminding me that everything is going to work out in the end, your words of encouragement have meant more to me than you know. Thanks again for everything.



A special thank you goes to all of the children who posed as entourage for my renderings. Thanks for your help!